

BUYER TIER 2 — CONFIDENTIAL · NOT FOR CONSTRUCTION

Residence Specification Sheet

Technical summary of design intent and specification basis for Cottage Type A and Villa Type A. Condo Type A specification will be issued separately.

Professional limitation: This document is a design intent summary prepared for buyer orientation only. It does not replace architectural, structural, civil, MEP, environmental, planning, fire or construction documents. All specifications are subject to detailed professional design, statutory approval, and site-specific survey confirmation. Not for construction. Artist's impression / design intent throughout.

Cottage Type A — Hillside Cottage

Plot references C-01 to C-06 / Six for-sale eco-luxury one-bedroom sanctuary cottages

FLOOR AREA SUMMARY

Space	Area (sq ft)
Enclosed interior	650 – 750
Covered veranda / deck	180 – 250
Outdoor shower / garden court	70 – 120
Entry / storage / service	50 – 90
Total experience area	900 – 1,100

STRUCTURAL SYSTEM

Primary frame: Marine-protected modular steel posts and beams — hot-dip galvanised or zinc-rich primer + marine epoxy + UV finish. Bolted connections, inspectable, separated from incompatible materials.

Secondary frame: Treated timber or engineered timber — soften the steel, support walls, decks, ceilings and screens.

Foundation: Light-touch piers, pads or micro-piles — confirmed by geotechnical and structural review. Raised construction to protect terrain and drainage.

Element	Specification Intent
Roof type	Butterfly or split-butterfly — signature Cottage Type A roof language. Standing-seam or concealed-fix metal in dark bronze, charcoal or green-black tone. Deep overhangs for shade and wall protection. Hurricane-tied with engineer-designed uplift connections.
Primary materials	Natural stone / locally sourced stone, lime/mineral plaster render, durable hardwood or thermally modified timber, premium metal roof
Wall finish (exterior)	Natural stone base, lime render or high-quality textured mineral finish. Timber cladding in durable hardwood, thermally modified timber, or approved mineral rainscreen
Wall finish (interior)	Lime/mineral plaster, warm neutral low-VOC paint, selective timber accents

Element	Specification Intent
Flooring	Engineered timber, premium porcelain stone or approved timber-look material suitable for humidity and cleaning
Ceiling	Timber-lined or timber-accented volume under the butterfly roof
Bathroom	Stone or porcelain slab, walk-in shower, refined fixtures, safe drainage. Timber cabinetry with stone or premium solid-surface vanity top
Glazing / openings	Hurricane-rated sliding, folding or fixed systems. Independent removable fine insect screens. Operating modes: open screened natural / closed conditioned-dehumidified
Joinery	Built-in wardrobe, minibar, luggage bench, owner storage — prevent clutter. Every touched element to feel intentional and durable.
Lighting	Warm, dimmable, low-glare and layered. No blue-white floodlit interior. No floodlighting of wetland edges.

MEP APPROACH

Mechanical: Quiet fan or dehumidified mode for sleeping suite. HVAC concealed and acoustically controlled. No visible service clutter in guest sightlines. Mechanical plant separated from guest arrival.

Electrical: Solar contribution where structurally appropriate. Warm LED dimmable throughout. No exposed utility clutter.

Plumbing: Reliable supply pressure, concealed runs, overflow-safe drainage. Outdoor shower drainage to safe collection point.

Communications: Concealed data/AV provisions to all key positions. No cable clutter in guest areas.



Villa Type A — Luxury Villa

Plot references V-01 to V-05 / Five for-sale luxury villas — southern estate, maximum privacy

FLOOR AREA SUMMARY

Space	Area (sq ft)
Enclosed interior	1,800 – 2,200
Covered veranda / pavilion	500 – 700
Private pool terrace	300 – 500
Outdoor / service areas	150 – 250
Total experience area	2,750 – 3,650

Subject to survey, structural and planning confirmation. Villa areas vary by plot position.

STRUCTURAL SYSTEM

Primary frame: Marine-grade structural system — steel, reinforced masonry, or hybrid as determined by structural engineer for hurricane-rated performance. Continuous load path from roof to foundations.

Secondary elements: Timber framing, screens, deck structure and architectural cladding system to be confirmed in detailed structural brief.

Foundation: Confirmed by geotechnical survey — type to be determined by engineer based on slope, soil and drainage conditions at each villa plot.

Element	Specification Intent
Roof type	Butterfly or mono-pitch — to be confirmed in Villa Gate 4 technical handoff. Hurricane-tied structure with engineer-designed uplift connections. Metal standing-seam or concealed-fix finish in dark bronze or charcoal tone.
Primary materials	Timber frame and cladding, natural stone (locally sourced), lime/mineral render, clay brick (where structurally appropriate), metal roof. Note: reclaimed timber is not used in SHER residential construction.
Exterior wall	Natural stone base, lime render panels, or stone/timber combination. No synthetic cladding systems. All exterior materials to weather authentically and require only natural maintenance regimes.
Interior	Lime/mineral plaster, warm low-VOC tones, engineered timber floors, timber ceiling elements. Open-plan living pavilion principle — fluid indoor-outdoor connection.
Bathroom(s)	Premium stone slab, large-format walk-in shower, freestanding bath where room programme allows, refined vanity, private outdoor bathing element. Multiple bathrooms per configuration.
Pool	Private plunge or lap pool at each Villa Type A position. Pool edge treatment, overflow system and landscape integration to be confirmed in detailed design. No floodlighting of pool toward conservation boundary.
Glazing / openings	Wide-format hurricane-rated openings — folding or sliding systems to the veranda and landscape edge. Fine insect screens. Full privacy capability when closed.

Element	Specification Intent
Lighting	Low-glare warm layered scheme. Exterior lighting strictly controlled — no habitat spillover toward wetland edges. No blue-white exterior fittings.

CONSERVATION CONTROLS (ALL RESIDENCES)

Control	Requirement
Wetland edge lighting	No floodlighting or directed beam lighting toward conservation zone edges, mangrove buffer, or bay. Warm low-lumen only within 30m of conservation boundary.
Utility clutter	No exposed services, meters, tanks, condensers or utility boxes in guest or owner sightlines. All services to be concealed, screened or positioned on the service side of the building.
Wildlife exclusion	Sealed soffits, screened vents, no decorative roosting cavities. Bat-safe construction details throughout.
Vegetation clearance	Minimal clearance for construction access only. No clearing beyond the building footprint and immediate service area. Planting plan required for each unit position.
Drainage	No direct run-off to the conservation zone or bay edge. Contained drainage to be confirmed by civil engineer per plot.

THE SIX DESIGN PILLARS — SHER CHARTER R02

These six pillars govern every design decision at SHER. Any element that fails one of these pillars is not a SHER element.

1. Preservation — Low-footprint foundations, limited clearing, protected drainage, conservation covenant compliance 2. Wellness — Clean air, calm sleep, generous bathing, screened nature connection, tactile natural materials 3. Tranquillity — No vehicle-dominated arrival, no visible service clutter, privacy from neighbours, night-time calm	4. Luxury — Crafted details, premium bathrooms, refined material junctions, effortless indoor-outdoor living 5. Safety & Resilience — Hurricane load path, insect and bat exclusion, moisture control, fire access planning, maintainable assemblies 6. Rebirth & Identity — A sanctuary that communicates renewal, privacy, protection and connection to Saint Lucian nature
---	---

Condo Type A specification: The Condo Type A (Lot E, 8 units) specification sheet will be issued separately as SHER-BUYER-005B-R01, following acceptance of the Condo visual record. The Condo uses a steel I-beam primary structural strategy distinct from the cottage and villa systems. Current design status: Gate 4 complete — visual acceptance pending.